

**Housing & Dining Services**

3500 Marine Street Room 122  
451 UCB, Boulder, Colorado 80309  
Phone: (303) 492-2465  
Fax: (303) 735-2375

**Williams Village Irrigation Delivery and Storage System  
PR#005794 / HSG# 10524****Addendum #2  
March 11, 2011****General Information**

1. This Addendum forms a part of the original Contract Documents, Drawings and Specifications for the above-referenced project. All parts of the original Drawings and Specifications shall remain in force except as noted below.
2. Refer to Information to Bidders, Paragraphs 1 and 11: The bid deadline remains 3:00 PM on Thursday, March 17, 2010.

**Questions from Bidders**

1. Please clarify the completeness of the CU provided components provided for this project, such as the package pump station. What must be supplemented by the General Contractor, if anything?

Answer: The irrigation vertical turbine pump station and discharge piping will be purchased and provided by the Owner. This includes shipping, offloading, and placement of pump station within the pump station building. The general contractor is responsible for connecting the provided discharge piping to the pump station and installing beneath the pump station floor to the exterior of the building. The general contractor is also responsible for completing all necessary electrical connections to the pump station for power supply to and from the station.

2. Please provide a copy the Army Corps of Engineers 404 Wetland Permit and the requirements for construction within the stream way of Bear Canyon Creek. Where are the terms of this permit available?

Answer: CU is providing the 404 Wetland Permit for the Army Corps of Engineers as well as the Section 401 Water Quality Certification from the Colorado Department of Public Health and Environment. The contractor for the raw water irrigation project will be responsible for all applicable construction-related, mitigation, and monitoring conditions that are contained in the permit and certification. The contractor will be required to meet with representatives of CU prior to commencing construction to go over specific requirements in these documents.

These documents have been posted to the CU website:

<http://www.colorado.edu/facilitiesmanagement/pdc/construction/open.html>

**END OF ADDENDUM #2**