

ASEN 4028: Senior Design Projects Spring 2021



Test Readiness Review

FLASH: Functional LiDAR Assessment of Structural Health


March 4, 2021



Team: Kunal Sinha, Ishaan Kochhar, Ricky Carlson, Fiona McGann, Jake Fuhrman, Shray Chauhan, Erik Stolz, Julian Lambert, Courtney Kelsey, Andrew Fu

Customer: ASTRA – Andrew Gisler, Chris Prince, Erik Stromberg

Advisor: Professor Dennis Akos







Overview





Motivation: Infrastructure Analysis

Statistics

- 614,387 bridges in the US
- 200,000+ are over 50 years old
- 17% of bridges are inspected annually
- Infrastructure monitoring market valued at \$1.78B in the U.S.

Motivation

• More precision, efficiency, and less manpower required per bridge is the goal



Schedule

Test Readiness



Objective & Mission Statement




Project Objective

The system shall provide a low-cost and efficient way to monitor and assess infrastructure.


Mission Statement

Design, build, and deploy a dynamic, vehicle-based LiDAR sensor package which will scan infrastructure while in motion to produce a high-quality 3D map/model that can be used by engineers to assess structural health.



Schedule


Test Readiness





Top-Level Design Overview








FLASH: Functional LiDAR Assessment of Structural Health

FLASH Concept of Operations

Single Infrastructure Inspection








FLASH: Functional LiDAR Assessment of Structural Health

FLASH Concept of Operations

Single Infrastructure Inspection







Critical Project Elements



| Designation | Element | Components | Why critical? | | |
|-------------|--------------------------------|---|---|--|--|
| CPE-1 | | | High-resolution, precise, and accurate data collection is key to insightful 3D mapping and model generation | | |
| CPE-2 | Data Processing Software | ROS* and SLAM*- based pipeline + commercial software package (CloudCompare) | Will require the most time and effort; consolidation of LiDAR and IMU data into a high-quality point cloud or mesh is not a straightforward process | | |
| CPE-3 | Vehicle Platform | Magnetic mounts + custom-fabricated housing | Sensor package must be secure up to highway speeds and must not pose a safety concern | | |

*ROS = Robot Operating System *SLAM = Simultaneous Localization and Mapping

Overview


Schedule

Test Readiness



Functional Block Diagram (FBD)






11



Software Design Overview






12



Software Design Overview

FLASH






HROS

Software Design Overview

FLASH






CloudCompare^{V2}

OpenGL (

eDF

Software Design Overview



Overview

Schedule > Te

Test Readiness > Budget

FLASH



Project Updates Since MSR



Hardware

- Received LiDAR unit from ASTRA
- Fit check performed with 3D-printed mount
- Ordered aluminum mount
- Successfully performed Pull Test

Software

- Completed ROS Master and startup scripts
- Finalized data file (.bag) structure
- Collected preliminary data (SSL test)
- Successfully installed LIO-SAM
- Finalized VIMS-Mono sub-components required for Ouster/LIO-SAM bridge








Schedule





Team Schedule: Software










Schedule: Structures and On-Board Setup









Test Readiness





Test Readiness Overview




| 01 | Structures | Fit CheckPull Test | |
|----|-------------|---|--|
| 02 | Software | ROS Scripts Carla Simulation Google Maps Comparison | Constructed to a reference interest 54 interest 54 interest 54 interest 54 interest 54 interest 56 int |
| 03 | Full System | Small Scale LiDAR Test Comprehensive Data Quality Test | 33.2 |

Schedule

Test Readiness



Test Overview






| Test Name | Duration | Pre | Status | Equipment | Location |
|--|----------|-----|--------|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) |
| Overview Schedule Test Readiness Budget 22 | | | | | |



Test Overview




| Test Name | Duration | Pre | Status | Equipment | Location | |
|--|----------|-----|--------|--|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space | |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment | |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) | |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass | |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) | |
| Overview Schedule Test Readiness Budget 23 | | | | | | |



Structures: Fit Check





LiDAR fits perfectly but the cable does not

Adjustments were made to accommodate cable

design

Overview

Schedule

Test Readiness





Objective/Rationale

Determine experimental "maximum" that the magnetic mounting can withstand to verify what the structure will be able to withstand during CST.

Validation of Model


Holding capacity tested with hook scale

Expected result: F_{mag} >> 1.6 lbf

Verifying DR 5.1


Withstanding drag forces associated with relative wind

Validated through Pull Test













Vehicle Roof



Belt with Hook Scale

3D-printed Structure with Magnets and Dummy Weight

Overview

Schedule




Test Readiness

Budget

Hook Scale Measurement







Schedule








Risk Reduction

Risk of LiDAR falling off vehicle proven to be extremely low

Test Importance

<u>System Safety</u>: LiDAR sensor proved to be safe against drag forces associated with driving at 65 mph.

<u>V&V</u>: Critical importance for project success.




Overview

Schedule

Test Readiness



Test Overview





| Test Name | Duration | Pre | Status | Equipment | Location |
|-------------------------------|----------|-----|---------|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) |
| | Overview | s | chedule | Test Readiness B | udget 30 |



Small-Scale LiDAR (SSL) Operational Test




Objective/Rationale

Baseline verification of stationary sensor performance and operation

General Procedure

- Scan test board at incremental distances (1 to 4 m) in shaded environment
- 2) Repeat in direct sunlight environment
- 3) Extract individual point cloud frames from saved data file for each test case (TBD)
- 4) Evaluate correspondence between point cloud data and true test board features/dimensions (TBD)



Schedule

Test Readiness



Small-Scale LiDAR (SSL) Operational Test




Risk Reduction

- LiDAR performance characterization before field deployment
- Ensure that data can be collected, stored, and viewed reliably
- Ensure that features can be discerned

Expected Result (Pass Criteria)

Identification of features at least <u>5 cm</u> in size from distances up to <u>4 meters</u> in shaded condition




Schedule

Test Readiness



Small-Scale LiDAR (SSL) Operational Test





Test Importance

Relevant Requirements:

- DR 2.2: Accuracy ≤ 10 cm (for range only)
- DR 2.3: Precision ≤ 10 cm
- FR 4: The on-board computer shall be capable of data storage, handling, and interfacing between components

<u>V&V</u>: Moderate importance for project success

Test Status: In Progress

Data has been collected on test board. Waiting on software pipeline for data assessment.


Overview

Schedule

Test Readiness



Test Overview






| Test Name | Duration | Pre | Status | Equipment | Location |
|-------------------------------|----------|-----|--------|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) |
| | udget 34 | | | | |



Software: Pipeline Validation Tests





Test Readiness

Budget

Schedule


Overview

35



Software: CARLA Simulation Flow Diagram







Software: CARLA Simulation



Objective/Rationale

Rapid test of software pipeline by providing raw LiDAR and IMU data of a virtual environment with the exact parameters of our sensor package.



General Procedure

- 1) Import map from CARLA Asset library of a bridge/structure to sample data
- 2) Set up simulation LiDAR Parameters to match Ouster's (from data sheet and orientation)
- 3) Connect simulated LiDAR to ROS Nodes in our script, record bag file
- 4) Play bag file in LIO-SAM and VINS-Mono algorithm to get Mesh
- 5) Take note of parameters to be changed and repeat from step 4

Screen capture of map to be imported onto CARLA

Overview

Schedule

Test Readiness





Software: CARLA Simulation



Test Importance

<u>SLAM Functionality:</u> a CARLA Simulation will prove that the output of SLAM can match ground truth data.



Verifying DR 3.1 and DR 7.1

Post processing efforts will be able to produce a useable 3D model outside of GNSS services.

Validation Method

Measurements of output will can be taken on Cloud Compare, will be compared with CARLA SImulated Map

Screen capture of map to be imported onto CARLA

Overview

Schedule

Test Readiness





Software: CARLA Simulation




Expected Result (Pass Criteria)

Generated LiDAR mesh from simulated asset with <u>10cm accuracy and precision</u>

Risk Reduction

- Give confidence in algorithm implementations
- Quick modifications to code without taking real data every time




Screen capture from ROS - CARLA integration tutorial





Test Overview





| Test Name | Duration | Pre | Status | Equipment | Location |
|-------------------------------|----------|-----|--------|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) |
| Overview Schedule | | | | Test Readiness Br | udget 40 |



Comprehensive System Test (CST)







Objective/Rationale

Complete system integration from real, raw 3D point cloud data to a deliverable 3D mesh. Project elements to be validated here include:

- Magnetic Attachment of Mount
- All Electrical Interfacing
- □ LiDAR 3D Point Cloud Collection
- □ Saving/Registering 3D Point Cloud Data
- Generating a Deliverable 3D Mesh

Test Environment: 6th Ave + Wadsworth, 3/23/21 at 1:00 PM **Equipment:** Complete system + vehicle

General Procedure (CONOPs)

- 1) Secure system to vehicle and verify power to all systems
- 2) Pass under the bridge/infrastructure of interest with LiDAR powered on
- 3) Collect, save, and register 3D point cloud data
- 4) Post-process data through custom pipeline to create a 3D mesh model of the infrastructure

Overview

Schedule

Test Readiness

Budget



Comprehensive System Test (CST)







Test Importance

Relevant Requirements:

• All Design Requirements

<u>V&V</u>: Critical importance to project success.

Validation Method

<u>Resolution:</u> Density will be calculated via tool within CloudCompare software.

<u>Accuracy:</u> Point cloud will be checked against stationary data and bridge clearance values from CDOT database (OTIS).

Test Schedule



Not Started

Requires all subteams to be ready and all other tests to be completed first.

Overview

Schedule

Test Readiness

Budget



Comprehensive System Test (CST)




Expected Result (Pass Criteria)

Creation of a <u>3D mesh</u> which meets <u>all</u> <u>Design Requirements</u> when compared to <u>ground truth data</u>

Risk Reduction

- Ensure that data can be collected, stored, and viewed
- Ensure system compatibility without error on a moving vehicle platform
- "Day-in-the-life" simulation of full system deployment as to be used by customer







Budget

Overview Schedule Test Readiness Budget



Procurement Updates



| Item | Quantity | Total Cost | Procurement Status | Lead Time | Criticality to Project Success** |
|---|----------|---------------|-----------------------|--------------|--|
| Lenovo Legion V Laptop | 1 | \$999.99 | Received | N/A | Desirable |
| Rubber Magnets (for Mounting) | 4 | \$59.40 | Received | N/A | Important |
| Power Inverter | 1 | \$35.96 | Received | N/A | Desirable |
| Ouster OS1-32 Gen 2 LiDAR | 1 | \$3,585.00* | Received | N/A | Critical |
| Mounting Structure (3D Printed - Plastic) | 1 | \$20.00 | Received | N/A | Important |
| Mounting Structure (CNC 6061 Aluminum) | 1 | N/A | On Order | ~2 weeks | Important |

**Criticality to upcoming testing schedule (all will be critical to project completion)

Overview

*ASTRA has purchased

> Schedule

Test Readiness

Budget



Procurement Updates



| Item | Quantity | Total Cost | Procurement Status | Lead Time | Criticality to Project Success** |
|---|----------|---------------|-----------------------|--------------|--|
| Lenovo Legion V Laptop | 1 | \$999.99 | Received | N/A | Desirable |
| Rubber Magnets (for Mounting) | 4 | \$59.40 | Received | N/A | Important |
| Power Inverter | 1 | \$35.96 | Received | N/A | Desirable |
| Ouster OS1-32 Gen 2 LiDAR | 1 | \$3,585.00* | Received | N/A | Critical |
| Mounting Structure (3D Printed - Plastic) | 1 | \$20.00 | Received | N/A | Important |
| Mounting Structure (CNC 6061 Aluminum) | 1 | N/A | On Order | ~2 weeks | Important |
| Total Funds Spent: \$1,171.83 Pilot Deposit: \$200.00 Remaining Funds: \$3,628.17 | | | | | |
| Overview Schedule Test Readiness Budget 46 | | | | | |



Updated Cost Plan



• Current Budget Estimate:

\$1,487.39

- Total Budget Allocated:
 - \$5,000.00
- Remaining Budget:
 - o \$3,512.61

| ASTRA has purchased |
|-------------------------|
| our OS1-32 LiDAR sensor |
| (\$3585.00) |

*Option (\$1,495.00) testing (D

| Subsystem | Total Cost (\$) |
|--------------------------------|--|
| Sensor Package | \$0* |
| Software | \$0 |
| Structures | (\$134.40) |
| Electronics/ Communications | (\$1035.95) |
| Total | (\$1170.35) |
| Cost Margin | 10% |
| Pilot Deposit | (\$200.00) |
| Total w/ Margin | (\$1487.39) |
| | Sensor Package Software Structures Electronics/ Communications Total Cost Margin Pilot Deposit |

Overview

Schedule

\$1,035.95

Test Readiness

Budget

Thank You!

21

Questions?

FUNCTIONAL LIDAR ASSESSMENT OF STRUCTURAL HEALTH





Backup Charts



Test Environment:

Parking Lot: 1055 Adams Cir Date: 2/22/21 Time: 2:00 PM MST Dry, Sunny Day (~50°F)

Equipment:

Belt Structural Housing Dummy Weight 2 Vehicles

Pull Test: Full Procedure



- 1. Park two cars of similar heights with trunks facing each other.
 - a. Park as close as possible.
- 2. Sit on roof of one car and attach the structural housing to the top of the other. Load dummy weight into the structural housing.
 - a. The back of the housing should be facing the tester.
- Attach a rope/belt around the rear (closest to the tester) two magnets in between the car and the base of the structure.
- 4. Attach the hook scale to the rope/belt.
- 5. Apply force steadily, noting when slippage happens.



Belt attached to around the rear two magnets for the pull test.



Pull Test: Take 1





| Hook Scale Reading | Observations (PT 1) | |
|--------------------|---|--|
| 5 lb | Sturdy (No slippage) | |
| 10 lb | Sturdy (No slippage) | |
| 20 lb | Sturdy (No slippage) | |
| 30 lb | Noise indicated slippage was starting to occur | |
| 35 lb | Slow, but steady slipping around 35 lbs | |



Pull Test: Take 2





| Hook Scale Reading | Observations (PT 2) |
|--------------------|-------------------------|
| 5 lb | Sturdy (No slippage) |
| 10 lb | Sturdy (No slippage) |
| 20 lb | Sturdy (No slippage) |
| > 30 lb* | Steady slippage occured |

* slippage occurred after 30 lbs of force, but before 35 lbs of force



Pull Test: Model Verification



Magnets must withstand the force of the oncoming wind created by the motion of the vehicle.

| <u>Variables:</u> Force From Wind Relative Wind (Car Speed) | F _w v | |
|---|---------------------|------------------------|
| <u>Constants:</u> Air Density (typical) Surface Area of | ρ | 1.14 kg/m ³ |
| Structural Housing: | Α | 99.9 cm ² |

Exposed Area Fwind Fmag $F_w = pressure * area = (\frac{1}{2} \rho v^2)*(A)$


@ 65 mph \rightarrow F_w = 4.8079 N = 1.0809 lbf w/ FOS = 1.5 \rightarrow F_w = 7.2119 N = 1.6213 lbf

Magnets must withstand at least 1.6213 lbf from a vertical pull test



Small-Scale LiDAR (SSL) Test Board





54



Small Scale LiDAR Test: Full Procedure

Test Environment: Garage Area: 5550 Pennsylvania Ave Date: 2/28/21 Time: 2:00 PM MST Dry, Sunny Day (~30°F)

Equipment:

LiDAR Sensor LiDAR Data Cable LiDAR Power Cable Laptop Test Board Paper Panels + Tape Tape Measure

- 1. Set up test board (see previous slide).
- 2. Set up markers at 1, 2, 3, and 4 meters away from the front of the LiDAR.
- 3. Set up test board at 1 meter mark at the same height as the LiDAR.
- 4. Open ROS Noetic code in Ubuntu 20.
 - a. Verify IP address of the LiDAR
 - b. Check source
 - c. Input .bag command
- 5. Run code to capture data for a small .bag file (~5 seconds).
- 6. Take screen capture of live stream (optional).
- 7. Repeat 5 and 6 at 2, 3, and 4 meters.
- Repeat steps 1 7 in different lighting conditions with different paper panels as desired.




Lighting condition 1 with 1st set of paper panels.




Lighting condition 2 with 2nd set of paper panels.




Small Scale LiDAR Test: Shaded, 1st Papers












Small Scale LiDAR Test: Shaded, 2nd Papers










57



Small Scale LiDAR Test: Sun, 2nd Papers












Software: Carla Simulation



Simulated Physical Environment

- Create <u>simple</u> test environment within simulated carla
- LiDAR sensor specifications and locations inputted
- Automatically add levels of noise or uncertainty to give more realistic outputs



CARLA Simulator - 3D LiDAR data plot https://www.youtube.com/watch?v=Mt08Ag57Vel January 2021

Realistic 3D LiDAR and IMU Outputs


 Enables rapid testing and development of post-processing software pipeline

Seamless Integration with ROS Noetic

- Dev build of software tested in real-time
- No risk to LiDAR unit during testing
- ROS Master and .bag behave exactly same as physical tests



Software: Carla Simulation



"lidar_point_cloud ", Cameras and Sensors, https://carla.readthedocs.io/en/stable/cameras_and_sensors/, Nov. 2020

- LiDAR: 32 channel, 10Hz, 50m range
- IMU: 6 axis, Accel. Gyro.
- Vehicle speed: (10 to 60mph), height: 1.6m
- Model: Simulated infrastructure



Requirement

A GNSS-independent post-processing technique shall be implemented to produce a point cloud from raw sensor data.

Validation Method

Carla will test our software pipeline by providing raw LiDAR and IMU data of a virtual environment with the exact parameters of our sensor package.

Expected Result

Lio-SAM registration and mapping will provide a point cloud that mirrors the virtual environment.



Comprehensive System Test: Full Procedure



Test Environment:

Bridge: 6th Ave + Wadsworth Date: 3/21/21 Time: 1:00 PM MST (1300)

Equipment:

LiDAR Sensor LiDAR Data Cable LiDAR Power Cable Structural Housing Laptop Power Inverter Power Adapter

- 1. Secure system to vehicle and verify power to all systems.
 - a. Secure structural housing to the top of testing vehicle.
 - i. We will be using Jake's car (2004 Chevrolet Trail Blazer)
 - b. Insert LiDAR sensor into structural housing and connect the LiDAR cable to the Laptop and power source inside of the car.
 - c. Turn on and verify power to Laptop
 - d. Open ROS code and verify LiDAR is operational via live stream.
 - e. Verify .bag files can be taken by capturing a small tester .bag file.



2.

Comprehensive System Test: Full Procedure



Pass under the bridge/infrastructure of

interest

with LiDAR powered on

- a. Drive to 6th Ave + Wadsworth Bridge
 - i. Following all laws and not
 - exceeding the speed limit. Collect, save, and register 3D point cloud

data

3.

- a. Begin taking data approximately 50 meters from the desired bridge.
- b. Stop taking data approximately 50 meters from the desired bridge.
- c. Verify that .bag file has been saved. Post-process data to create a 3D mesh

4. model

of the infrastructure.


- a. Return
- b. Load in .bag file to LIO-SAM and VINS Mono code.
- c. Load the resulting point cloud into Cloud

Notes

- Multiple passes are not needed because this is meant to verify the functionality of the system. This test will only have one pass under the bridge. Based on the results, the team may decide multiple passes are needed for future data collection.
- Verification of the LiDAR's accuracy will come from comparing our generated 3D mesh to CDOT data.
- Verification of the point cloud density will occur within the post processing phase by utilizing tools within the Cloud Compare software.



Test Overview






| Test Name | Duration | Pre | Status | Equipment | Location |
|-------------------------------|----------|-----|--------|--|--|
| Structures: Pull Test | 1 week | NA | | Hook scaleMount + magnets | Open parking space |
| Small Scale LiDAR Test | 1 week | 2 | | Test boardLiDAR sensor + laptop | Controlled indoor + outdoor environment |
| CARLA Simulation Test | 20 days | NA | | Processing computer | Homebase (with WiFi) |
| Comprehensive System Test | 2 weeks | 2 | | LiDAR sensor + laptop Mount + magnets Vehicle Electrical hardware | Low-traffic road with a highway underpass |
| Google Maps API Comparison | 2 weeks | 4 | | Processing computer | Homebase (with WiFi) |



Comprehensive System Test: Google Maps API Comparison







Google Maps API overlay

- Generated point cloud of chosen infrastructure using Lio-SAM method
- API map of chosen infrastructure

Requirements

The point cloud data shall be combined with the localization data to create a **3D mesh**.

Validation Method

Google Maps API will provide true X/Y position that our mesh will be compared against.

Expected Result

Point cloud data from the Ouster will mirror X/Y of Google Maps API and any drift errors will be quantified



Google Maps API Comparison




Risk Reduction


This test will reduce the risk of project failure by verifying that the location data received from the LiDAR is accurate enough when compared to a control.

Test Importance

Data Quality: This test will give the team further confidence of the validity of the data received.

<u>V&V</u>: Mild Importance once successfully completed







System Integration Plan



Structures


- Magnetic attachment to vehicle
- Provides thermoregulation
- Accommodates interface cable

Electronics

- Input power from the vehicle
- Inverter distributes power to all necessary components

Software

- UDP Ethernet connection from LiDAR interface box to laptop
- WiFi-enabled for data transfer



Schedule

Test Readiness





Comprehensive System Test: Locations



6th Ave. over Wadsworth Blvd. (Built 1972)



I-70 over Kipling Street (Built 1967)



I-70 over Harlan Street (Built 1967)

These bridges clearly exhibit structural deficiencies in the form of cracking, spalling, corrosion, delamination, and deformation

Source: Google Maps, Denver7 News



Housing Dimensions



