
UNIVERSITY OF COLORADO DESIGN AND CONSTRUCTION STANDARDS TECHNICAL DRAWINGS


TABLE OF CONTENTS

| Page | Drawing Title Drawing Number |
|------|--|
| C.01 | Utility Trench 16" or Less |
| C.02 | Utility Trench Wider than 16 " |
| C.03 | Pipe Bedding |
| C.04 | Water Line Lowering - Utility Line Crossing Only |
| C.05 | Water Line Lowering - Culvert Crossing and Irrigation Ditch Crossing |
| C.06 | Water Line Lowering - Drainageway Crossing Only |
| C.07 | Sewer Crossing |
| C.08 | Valve Box |
| C.09 | Fire Hydrant Placement |
| C.10 | Fire Hydrant Installation - Types 1, 2, and 3 |
| C.11 | Horizontal Thrust Block |
| C.12 | Vertical Thrust Block |
| C.13 | Standard Sewer Manhole |
| C.14 | Standard Drop Sewer Manhole |
| C.15 | Manhole Invert |
| C.16 | Standard Manhole Bolt-Down Water-Tight Frame and Cover |
| C.17 | Polypropylene Reinforced Plastic Manhole Step |
| C.18 | Sewer Service Line |
| C.19 | Storm Sewer Manhole |
| C.20 | Storm Sewer Manhole Base |
| C.21 | Flat Top for Shallow Manholes Less Than 6' in Height |
| C.22 | Fire Hydrant Landscape Setback Minimums |
| C.23 | Utility Bridging |
| C.24 | Pipe Casing with Casing Spacers |
| C.25 | Length of Restrained Pipe |
| C.26 | Mechanical Seal Wall Penetration |
| C.27 | Pedestrian Light Standard Details |
| C.28 | Stormwater BMP |
| C.29 | Concrete Washout BMP |
| C.30 | Silt Fence BMP |
| C.31 | Erosion Logs BMP |
| C.32 | Tracer Wire Placement |
| C.33 | Magnetized SnakePit |
| C.34 | Joining Tracer Wire Lug Connection |
| C.35 | Joining Tracer Wire Cad Weld Connection |
| C.36 | Grounding Anode |
| C37 | Porous Pavers Edge Detail |

C.38 Porous Pavers Detail (Adjacent to Building)

- C.39
- Tunnel Penetration Sealing (Live Utilities)
 Tunnel Penetration Sealing (Abandoned Utilities) C.40





TYPICAL TRENCH SECTION


NOTES:


- 1. MINIMUM COVER TO BE BELOW OFFICIAL STREET GRADE.
- MINIMUM DISTANCE BETWEEN EDGE OF TRENCH AND EDGE OF ASPHALT, OR LIP OF CURBLINE, SHALL BE 3 FEET.
- REFER TO DRAWING NO. C.04 FOR PAVEMENT RESTORATION FOR PAVEMENT LESS THAN 3 YEARS OLD.
- ON STATE HIGHWAYS, REFER TO CDOT UTILITY REQUIREMENTS.

TRENCH WIDTH

| PIPE DIAMETER | MINIMUM WIDTH | MAXIMUM WIDTH |
|------------------|------------------|------------------|
| 6" | 1' - 6'' | 2' - 6'' |
| 8" | 1' - 8'' | 2' - 8'' |
| 12" | 2' - 0'' | 3' - 0'' |
| 16" | 2' - 4'' | 3' - 4'' |
| 20'' | 2' - 8'' | 3' - 8'' |
| 24" | 3" - 0" | 4' - 0'' |

| DRAWN BY: CHECKED BY: | University of Colorado | ISSUED: JULY, 1999 |
|-----------------------|------------------------|--------------------|
| APPROVED BY: | UTILITY TRENCH | DRAWING NO. |
| | WIDER THAN 16" | C.02 |
| APPROVED BY: | | |





DRAWN BY: WMJ

CHECKED BY:

APPROVED BY:

University of Colorado


AND JOINT RESTRAINT AS SPECIFIED

WATER LINE LOWERING

UTILITY LINE CROSSING ONLY

ISSUED: JULY, 1999 REVISED: JULY, 2014

DRAWING NO.



NOTE: PIPE RESTRAINT SHALL BE BOTH CONCRETE THRUST BLOCKS AND JOINT RESTRAINT AS SPECIFIED.

DRAWN BY: WMJ

CHECKED BY:


APPROVED BY:

University of Colorado

WATER LINE
LOWERING
CULVERT CROSSING AND
RIGATION DITCH CROSSING

ISSUED: JULY, 1999 REVISED: JULY, 2014

DRAWING NO.



NOTE: PIPE RESTRAINT SHALL BE BOTH CONCRETE THRUST BLOCKS AND JOINT RESTRAINT AS SPECIFIED.

DRAWN BY: WMJ

CHECKED BY:


APPROVED BY:


University of Colorado

WAILR LINE LOWERING Drainageway crossing only ISSUED: JULY, 1999

REVISED: JULY, 2014

DRAWING NO.





- 1. OPERATING NUT SHALL BE EXTENDED WITHIN 4 FEET OF SURFACE.
- 2. EXTENSION STEMS REQUIRED WHERE VALVE IS AT DEPTH GREATER THAN 5 FEET.

DRAWN BY: SW

CHECKED BY:


APPROVED BY:

University of Colorado

SEWER CLEANOUT VALVE BOX ISSUED: JULY, 1999 REVISED: JUNE, 2014

DRAWING NO.

C.08a



- 1. OPERATING NUT SHALL BE EXTENDED WITHIN 4 FEET OF SURFACE.
- 2. EXTENSION STEMS REQUIRED WHERE VALVE IS AT DEPTH GREATER THAN 5 FEET.

DRAWN BY: SW

CHECKED BY:


APPROVED BY:


University of Colorado
SEWER CLEANOUT
VALVE BOX—ARCHITECTURAL
FINISH


ISSUED: JULY, 1999 REVISED: JUNE, 2014


DRAWING NO.

C.08b










11 1/4°, 22 1/2°, 45° AND 90° BENDS

MINIMUM BEARING SURFACE AREA IN SQUARE FEET

| SIZE | TEE AND PLUG | 90° BEND | 45 ° BEND | 22 1/2° BEND | 11 1/4° BEND |
|------|-----------------|-------------|--------------|-----------------|-----------------|
| 4" | 2.0 | 2.5 | 1.5 | 1.0 | 1.0 |
| 6" | 4.0 | 5.5 | 3.0 | 1.5 | 1.0 |
| 8" | 6.5 | 9.0 | 5.0 | 2.5 | 1.5 |
| 10" | 10.0 | 14.0 | 7.5 | 4.0 | 2.0 |
| 12" | 14.0 | 20.0 | 11.0 | 5.5 | 3.0 |
| 14" | 19.0 | 27.0 | 14.5 | 7.5 | 4.0 |
| 16" | 25.0 | 35.0 | 19.0 | 10.0 | 5.0 |
| 18" | 31.5 | 44.5 | 24.0 | 12.5 | 6.5 |
| 20" | 38.0 | 54.5 | 29.5 | 15.0 | 7.5 |
| 24" | 55.5 | 78.5 | 42.5 | 22.0 | 11.0 |



TYPICAL CROSS SECTION

NOTES:

- BASED ON 250 PSI MAXIMUM PRESSURE AND 2000 LBS/FT² BEARING CAPACITY.
- 2. ALL FITTINGS MUST BE WRAPPED WITH POLYETHYLENE TO PREVENT CONCRETE FROM ADHERING TO BOLTS OR PIPES.
- 3. MAXIMUM JOINT DEFLECTION WITHOUT REACTION BLOCK IS 1+1/2°.
- 4. CONCRETE SHALL DEVELOP 3,000 PSI AT 28 DAYS.
- 5. JOINTS AND BOLTS SHALL BE ACCESSIBLE FOR REPAIRS.
- 6. ALTERNATVE THRUST BLOCK DESIGNS, BASED ON LOCAL SOIL CONDITIONS AS ASSESSED BY A LICENSED GEOTECHNICAL ENGINEER, WILL BE ALLOWED WITH WRITTEN APPROVAL FROM THE UCB CIVIL ENGINEER.

DRAWN BY:


CHECKED BY:


APPROVED BY:


University of Colorado

HORIZONTAL Thrust block ISSUED: JULY, 1999 REVISED: JULY, 2014

DRAWING NO.











| *A* | *B* |
|----------|----------|
| PIPE DIA | PIPE DIA |
| 8* | 8" |
| 10* | 10" |
| 12* | 12" |
| 15* | 12" |
| 18* | 15" |
| 21* | 18" |
| 24" | 18" |
| 27" | 18" |
| 30" | 18* |
| 36" | 18" |
| 42" | 24* |
| 48" | 30* |


University of Colorado DRAWING NO. C.14














DRAWN BY:

CHECKED BY:

APPROVED BY:


University of Colorado


STORM SEWER Manholf base ISSUED: JULY, 1999


REVISED: MAY 2009

DRAWING NO.

0.20







DRAWN BY: WMJ

CHECKED BY:

APPROVED BY:


University of Colorado

UTILITY BRIDGING

ISSUED: April 15, 2010

REVISED:

DRAWING NO.



| CARRIER PIPE | CASING PIPE | | | |
|--------------|-------------|----------------|--|--|
| NOMINAL DIA | MIN OD | MIN WALL THICK | | |
| 6" | 16" | 0.250" | | |
| 8" | 18" | 0.282" | | |
| 12" | 22" | 0.344" | | |
| 16" | 28" | 0.406" | | |
| 20" | 32" | 0.469" | | |

DRAWN BY: WMJ

CHECKED BY:

APPROVED BY:


UNIVERSITY OF COLORADO

PIPE CASING WITH CASING SPACERS

ISSUED: JUNE 5, 2012

REVISED:

DRAWING NO.



LENGTH OF RESTRAINED PIPE

| NOMINAL PIPE DIAMETER | 4" | 6" | 8" | 12" | 16" | 20" | 24" |
|-------------------------------|-----|-----|-----|-----|------|------|------|
| 90 DEG BEND, TEE, DEAD END | 30' | 45' | 60' | 86' | 108' | 132' | 155' |
| VALVE | 30' | 45' | 60' | 86' | 108' | 132' | 155' |
| 45 DEG BEND | 9' | 13' | 18' | 25' | 32' | 39' | 45' |
| 22.5 DEG BEND | 2' | 4' | 5' | 7' | 8' | 10' | 12' |
| 11.25 DEG BEND | 2' | 2' | 2' | 2' | 2' | 3' | 3' |

NOTES: 1. LENGTH OF RESTRAINED

PIPE MEASURED EACH WAY FROM VALVES AND BENDS.
2. CROSSES MUST BE RESTRAINED IN ALL DIRECTIONS.
3. WHEN REDUCERS ARE USED ON A VALVE INSTALLATION THE LENGTH OF RESTRAINT SHALL BE BASED ON PIPE SIZE NOT VALVE SIZE.

DRAWN BY: WMJ

CHECKED BY:

APPROVED BY:

UNIVERSITY OF COLORADO


LENGTH OF

RESTRAINED PIPE

ISSUED: JUNE 2012

REVISED:

DRAWING NO.



- 1. CORE DRILL OPENING PER SEAL MANUFACTURER'S REQUIREMENTS FOR EXISTING WALLS.
- 2. INSIDE DIAMETER OF SLEEVE SHALL BE DETERMINED ACCORDING TO SEAL MANUFACTURER'S REQUIREMENTS DEPENDING ON CARRIER PIPE OUTSIDE DIAMETER.
- 3. INTERMEDIATE WATERSTOP TO BE CENTERED WITHIN WALL UNLESS NOTED OTHERWISE.

DRAWN BY: WMJ

CHECKED BY:

APPROVED BY:

UNIVERSITY OF COLORADO


MECHANICAL SEAL

WALL PENETRATION

ISSUED: JUNE 2012

REVISED:

DRAWING NO.



- 1. DIMENSIONS FOR THE ANCHOR BASE AND ANCHOR BOLTS ARE VARIABLE FOR THE HEIGHT OF THE LIGHT STANDARD AND THE MAST ARM CONFIGURATION. ALL COMPONENTS SHALL FIT AND ACCOMMODATE THE REQUIREMENTS OF THE LIGHT STANDARD SUPPLIED. FIELD MODIFICATIONS ON ANY COMPONENTS SHALL BE APPROVED BY A LICENSED STRUCTURAL ENGINEER AND UCB.
- 2. FOUNDATION SHALL BE 7 FT. FOR LIGHT STANDARDS 20 FT. THROUGH 40 FT., AND 6 FT. FOR LIGHT STANDARDS LESS THAN 20 FT.
- 3. LIGHT STANDARD FOUNDATION DEPTH IS BASED ON A MAXIMUM POLE HEIGHT OF 40 FT. IN STIFF CLAY WITH N > 8 OR MEDIUM SAND WITH N > 15 AS DETERMINED BY ASTM D 1586 STANDARD PENETRATION TEST.
- 4. FOUNDATIONS FOR LIGHT POLE STANDARDS HIGHER THAN 40 FT. OR LIGHT STANDARDS WITH MULTIPLE LUMINARIES OR BANNERS, OR VARYING SOIL OR WIND CONDITIONS, SHALL BE DESIGNED BY A LICENSED ENGINEER.
- 5. CONCRETE SHALL BE CLASS B, 4000 PSI COMPRESSIVE STRENGTH, WITH A MAXIMUM WATER CONTENT OF 0.48 AND A SLUMP OF 1" TO 4".
- 6. LIGHT POLE FOUNDATIONS SHALL EXTEND 3 FT. ABOVE GRADE IN PARKING LOTS AND 4 IN. ABOVE GRADE IN ALL OTHER LOCATIONS.

DRAWN BY: WMJ
CHECKED BY:


APPROVED BY:

UNIVERSITY OF COLORADO
PEDESTRIAN LIGHT
STANDARD DETAIL


ISSUED: AUG 2013

REVISED:


DRAWING NO.



PLAN VIEW OF INLET PROTECTION NTS



PLAN VIEW OF INLET PROTECTION FOR MULTIPLE BAGS NTS



PLAN VIEW OF GRATE INLET PROTECTION NTS

| LENGTH OF INLET (L) | NUMBER OF GRAVEL BAGS UPSTREAM OF INLET |
|------------------------|--|
| 0' - 5' | 1 |
| 6' - 10' | 2 |
| L > 10' | 3 |

Notes:

- -Gravel bag shall be placed tightly against curb face and shall be placed 5'upstream from the inlet opening.
- -Top of gravel bag shall be 1" below top of curb

DRAWN BY: RWC

CHECKED BY:

APPROVED BY:

University of Colorado, Boulder


STORMWATER BMP

ISSUED: 11/22/13

REVISED:

DRAWING NO.


C - 28




- 1. A PLASTIC FENCE SHALL BE INSTALLED AROUND THE CONCRETE WASHOUT AREA, EXCEPT AT THE OPENING.
- 2. WASHOUT FACILITY SHALL BE LOCATED A MINIMUM OF 50 FT. FROM STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, AND WATERCOURSES UNLESS OTHERWISE AUTHORIZED BY THE UCB CIVIL ENGINEER.
- 3. TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE CONSTRUCTED ABOVE GRADE OR BELOW GRADE AT THE OPTION OF THE CONTRACTOR. WASHOUT FACILITY SHALL BE CONSTRUCTED AND MAINTAINED IN SUFFICIENT QUALITY AND SIZE TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- 4. ALL WASHOUT FACILITIES SHALL HAVE ADEQUATE PROTECTION AVAILABLE IN CASE OF RAIN AND ADVERSE WEATHER.
- 5. PREFABRICATED WASHOUTS MAY BE USED IF APPROVED BY THE UCB CIVIL ENGINEER.
- 6. CONCRETE WASHOUTS SHALL BE CONSTRUCTED/POSITIONED IN A WAY AS TO NOT CAUSE ANY FLOODING INTO CAMPUS FACILITIES.
- 7. THE CONTACTOR SHALL ASSUME SOLE MONETARY RESPONSIBILITY FOR ANY CLEAN-UP RESULTING FROM IMPROPER CONCRETE WASHOUT PRACTICES.

DRAWN BY: RWC University of Colorado, Boulder University of Colorado, Boulder REVISED:

APPROVED BY: CONCRETE WASHOUT DRAWING NO. C-29




- -GEOTEXTILE SHALL BE ATTACHED TO WOOD POST WITH THREE OR MORE STAPLES PER POST.
- -STAPLES SHALL BE 1"
- -WOOD POST SHALL BE 12" x 12" NOMINAL









JOINING SECTION DETAIL NTS

-REQUIRED AT EVERY JOINT

-FOLD GEOTEXTILE AROUND EACH POST ONE FULL TURN.
SECURE GEOTEXTILE TO POST WITH THREE STAPLES MINIMUM.
POSTS SHALL BE TIGHTLY ABUTTED WITH NO GAPS TO
PREVENT POTENTIAL FLOW-THROUGH OF SEDIMENT AT JOINT.

NOTES:

- 1. FILTER FABRIC SHALL CONFORM TO THE REQUIREMENTS DESCRIBED IN SECTION 420 OF CDOT'S STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND SECTION 02230 OF THE UCB STANDARD SPECIFICATIONS.. MINIMUM HEIGHT OF THE FILTER FABRIC SHALL BE 36".
- 2. USE OF JOINTS SHOULD BE MINIMIZED TO IMPROVE THE STRENGTH AND EFFICIENCY OF THE BARRIER.
- 3. POSTS FOR SILT FENCES SHALL BE METAL OR HARD WOOD. WODDEN POSTS SHALL HAVE A MINIMUM DIAMETER OR CROSS SECTION OF $1\frac{1}{4}$ ". METAL POSTS SHALL BE "STUDDED TEE" OR "U" TYPE WITH A MINIMUM WEIGHT OF 1.33 LBS/FT, AND THEY SHALL BE PROTECTED AGAINST CORROSION. METAL POSTS SHALL HAVE PROJECTIONS FOR FASTENING WIRE.
- 4. INSTALLATION OF SILT FENCE WILL NOT BE LOCATED WITHIN DRIP LINES OF EXISTING TREES.
- 5. WHEN USED, WIRE FENCE REINFORCEMENT FOR THE FILTER FABRIC SHOULD BE A MINIMUM OF 36" IN HEIGHT AND A MINIMUM OF 14 GAUGE, WITH A MAXIMUM MESH SPACING OF 6".
- 6. SILT FENCES USED AT TOE OF SLOPES SHALL BE PLACED 5' TO 10' BEYOND TOE OF SLOPE TO PROVIDE STORAGE CAPACITY.

DRAWN BY: RWC

CHECKED BY:

APPROVED BY:

University of Colorado, Boulder

SILT FENCES


ISSUED: 12/11/13

REVISED:

DRAWING NO.

(-30)


EROSION LOG DITCH INSTALLATION



NOTES:

- 1. POINTS A SHALL BE A MINIMUM OF 1' HIGHER THAN POINT B.
- 2. EROSION LOGS SHALL BE EMBEDDED 2 INCHES INTO THE SOIL.
- 3. WOODEN STAKES SHALL BE 1½" x 1½" NOMINAL AND EMBEDDED TO A MINIMUM DEPTH OF 12".
- 4. EROSION LOGS SHALL BE TIGHTLY ABUTTED WITH NO GAPS.

EROSION LOG FILTER AT DROP INLET



1. LOCATE EROSION LOGS AT THE OUTSIDE EDGE OF THE CONCRETE APRON

DRAWN BY: **RWC**

CHECKED BY:

APPROVED BY:

University of Colorado, Boulder


EROSION LOGS


ISSUED: 12/09/13

REVISED:

DRAWING NO.


C - .31






- 1. TRACER WIRE FOR ALL UTILITIES SHALL BE BROUGHT UP TO SURFACE OUTSIDE OF PIPE AND TERMINATED IN TEST STATION AS SHOWN. ACCESS POINTS SHALL BE LOCATED AT LEAST EVERY 250 FEET, AND AT EVERY POINT WHERE THE UTILITY SERVED BY THE TRACER WIRE HAS ANOTHER PHYSICAL ACCESS POINT. SEE DETAIL C34 FOR SNAKE PIT DETAILS ALONG UTILITY LINES.
- TRACER WIRE SHALL BE INSTALLED IN A CONTINUOUS FASHION BETWEEN ACCESS POINTS.IF A TRACER WIRE MUST BE JOINED BELOW GROUND, WIRE MUST BE JOINED IN PERMANENT BOND. SEE EITHER DETAIL C34 OR C35, WHICHEVER APPLIES.
- TRACER WIRE SHALL BE ATTACHED TO TOP OF PIPE THROUGH TAPE OR PLASTIC WIRE AT 5-8 FOOT INTERVALS, EXCEPT FOR FUEL AND GAS LINES WHICH ARE TO BE FASTENED USING COPPERHEAD TRACERSPACER AT THE SAME INTERVAL. TRACER WIRE SHALL BEGIN AND TERMINATE AT A COPPERHEAD SUPER ROD MAGNESIUM ANODE. SEE DETAIL C35.

ISSUED: DRAWN BY: FM-JB University of Colorado CHECKED BY: TRACER WIRE DRAWING NO. APPROVED BY: PLACEMENT




- TRACER WIRE FOR ALL UTILITIES SHALL BE BROUGHT UP TO SURFACE OUTSIDE OF PIPE AND TERMINATED IN TEST STATION AS SHOWN. ACCESS POINTS SHALL BE LOCATED AT LEAST EVERY 250 FEET, AND AT EVERY POINT WHERE THE UTILITY SERVED BY THE TRACER WIRE HAS ANOTHER PHYSICAL ACCESS POINT.
- TRACER WIRE SHALL BE INSTALLED IN A CONTINUOUS FASHION BETWEEN ACCESS POINTS. IF A TRACER WIRE MUST BE JOINED BELOW GROUND, WIRE MUST BE JOINED IN PERMANENT BOND. SEE EITHER DETAIL C34 OR C35, WHICHEVER APPLIES.
- 3. TRACER WIRE SHALL BE ATTACHED TO TOP OF PIPE THROUGH TAPE OR PLASTIC WIRE AT 5-8 FOOT INTERVALS, EXCEPT FOR FUEL AND GAS LINES WHICH ARE TO BE FASTENED USING COPPERHEAD TRACERSPACER AT THE SAME INTERVAL.
- 4. TRACER WIRE SHALL BEGIN AND TERMINATE AT A COPPERHEAD SUPER ROD MAGNESIUM ANODE. SEE DETAIL C35.

| DRAWN BY: FM-JB CHECKED BY: | University of Colorado | ISSUED: REVISED: |
|-----------------------------|------------------------|------------------|
| APPROVED BY: | MAGNETIZED SNAKEPIT | drawing no. |




STEP 3



NOTES:


- 1. STRIP 5/8" OF INSULATION FROM END OF EACH WIRE.
- 2. INSERT TWO STRIPPED ENDS FIRMLY INTO DIRECT BURY WIRE NUT.
- 3. TWIST WIRE NUT CLOCKWISE WHILE PUSHING
- WIRES FIRMLY INTO NUT.
 SONNECTOR VARIES BY APPLICATION AND UTILITY, REFER TO STANDARD 02410 FOR DETAILS.

STEP 2




PLACE LUG ON MAIN WIRE

STEP 4



INSERT BRANCH WIRE INTO LUG. **TIGHTEN** SCREWS AND REMOVE **SEALANT** COVER



DRAWN BY: FM-JB

CHECKED BY:

APPROVED BY:


University of Colorado


JOINING TRACER WIRE LUG CONNECTION

ISSUED:

REVISED:

DRAWING NO.





DRAWN BY: FM-JB

CHECKED BY:

APPROVED BY:


University of Colorado

GROUNDING ANODE

ISSUED:

REVISED:


DRAWING NO.



- 1. PERVIOUS PAVEMENT SYSTEM SHALL CONFORM TO UCB STANDARD 02515 OR APPROVED ALTERNATIVE. WRITTEN APPROVAL FROM UCB CIVIL ENGINEER IS REQUIRED FOR ALTERNATIVE SYSTEM.
- 2. UCB INSPECTOR SHALL OBSERVE PLACEMENT OF GEOTEXTILE, SUB-BASE COURSE, BASE COURSE, BEDDING COURSE AND PAVERS.
- 3. A TESTING AGENCY SHALL CONDUCT IN-PLACE DENSITY TESTING PER ASTM D 4254, OR APPROVED ALTERNATIVE. WRITTEN APPROVAL FROM UCB CIVIL ENGINEER IS REQUIRED FOR ALTERNATIVE DENSITY TESTING METHODS.
- 4. ALL TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING AND INSPECTION AGENCY EMPLOYED BY UCB.
- 5. INSTALLATION CONTRACTOR SHALL RETURN TO SITE AFTER 11 MONTHS FROM COMPLETION OF WORK AND PROVIDE INITIAL MAINTENANCE AS REQUIRED BY UCB CIVIL ENGINEER WITH NO ADDITIONAL COMPENSATION.

NTS

| DRAWN BY: GP CHECKED BY: | University of Colorado | ISSUED: JULY 2016 REVISED: |
|--------------------------|------------------------------|----------------------------|
| WM APPROVED BY: JA | POROUS PAVERS EDGE DETAIL | drawing no. |




- 1. PERVIOUS PAVEMENT SYSTEM SHALL CONFORM TO UCB STANDARD 02515 OR APPROVED ALTERNATIVE. WRITTEN APPROVAL FROM UCB CIVIL ENGINEER IS REQUIRED FOR ALTERNATIVE SYSTEM.
- REFER TO UCB TECHNICAL DETAIL C37 FOR PERVIOUS PAVEMENT SYSTEM.
- EXTEND EPDM IMPERMEABLE SHEET MEMBRANE MINIMUM 5 FEET UNDER PERVIOUS PAVEMENT SYSTEM. CONTRACTOR SHALL SUMBIT DESIRE PRODUCT TO UCB CIVIL ENGINEER FOR REVIEW AND APPROVAL FOR IMPERMEABLE EPDM SHEET MEMBRANE AND IMPERMEABLE JOINT SEALANT.
- UCB INSPECTOR SHALL OBSERVE PLACEMENT OF GEOTEXTILE, SUB-BASE COURSE, BASE COURSE, BEDDING COURSE AND PAVERS.
- 6. A TESTING AGENCY SHALL CONDUCT IN-PLACE DENSITY TESTING PER ASTM D 4254, OR APPROVED ALTERNATIVE. WRITTEN APPROVAL FROM UCB CIVIL ENGINEER IS REQUIRED FOR ALTERNATIVE DENSITY TESTING METHODS.
- ALL TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING AND INSPECTION AGENCY EMPLOYED BY UCB.
- INSTALLATION CONTRACTOR SHALL RETURN TO SITE AFTER 11 MONTHS FROM COMPLETION OF WORK AND PROVIDE INITIAL MAINTENANCE AS REQUIRED BY UCB CIVIL ENGINEER WITH NO ADDITIONAL COMPENSATION. NTS


DRAWN BY: GP CHECKED BY: WM APPROVED BY:

JA

University of Colorado POROUS PAVERS DETAIL (ADJACENT TO BUILDING) ISSUED: JULY 2016 REVISED:

DRAWING NO.





- 1. WATERPROOFING SYSTEM SHALL CONFORM TO UCB STANDARDS SECTION 07110, 07120, AND 07160. WRITTEN APPROVAL FROM UCB CIVIL ENGINEER IS REQUIRED FOR ALTERNATIVE WATERPROOFING SYSTEM.
- 2. CUT EXISTING UTILITY LINE 2' MINIMUM AWAY FROM TUNNEL EXTERIOR WALL UPON APPROVAL FROM UCB CIVIL ENGINEER.
- CAP EXISTING UTILITY LINE. CONTRACTOR SHALL SUBMIT DESIRED PRODUCT TO UCB CIVIL ENGINEER FOR REVIEW AND APPROVAL. ENSURE WATERPROOFING FOR UTILITY CAP. SUFFICIENT STRENGTH IS REQUIRED TO WITHSTAND HYDROSTATIC AND/OR EARTH PRESSURES.

NTS

DRAWN BY: JB, GP

CHECKED BY:

WM

APPROVED BY:

JA

University of Colorado
TUNNEL PENETRATION
SEALING
(ABANDONED UTILITIES)

ISSUED: NOV 2015
REVISED:

DRAWING NO.