




# 2025 CU Boulder Hydropower Collegiate Competition Team

## Conceptual Design and Testing



Alexandra "Sascha" Fowler | Sára Leschová | Patrick Liu | Charlie Loewenguth | Landon Natrass | Jack Printup | Miles Salzer | Maximilian Schmid | Luke Shaw | Pisay Suzuki | Tristan Wrable


### Motivation and Background



Generation	
Duration	8 Hours
Average Flowrate	2.8 m/s
Number of Turbines	4
Best Efficiency Point	91%
Energy Produced	3.84 GWh


Pumping	
Duration	16 Hours
Average Flowrate	1.4 m/s
Number of Pumps	4
Maximum Efficiency	93%
Volume Pumped	4.4 Billion Liters

### Critical Powerhouse Components




- Pelton Turbine**
- 4.32-meter diameter
  - Produces 119 MW
  - Selected based on power specific speed
  - Controlled by Oil Pressure Governor
  - Must operate above maximum water line

- Salient Pole Synchronous Generator**
- 6 poles, 1,200 RPM
  - Rated for 146 MVA
  - Stator generates 3 phase voltage
  - Rated to handle turbine runaway speeds



- Multi-stage Centrifugal Pump**
- Diffuser Guide Vanes
  - Shrouded impellers
  - 3 stages, double suction
  - Operates 10 feet below minimum water line


### Piping Design




### Building and Testing

Testing Goals		Site Water Analysis		
<ul style="list-style-type: none"><li>• Analysis of local factors<ul style="list-style-type: none"><li>○ Scaling and corrosion</li></ul></li><li>• Validation of theoretical model</li><li>• Repeated testing of physical full-scale model</li><li>• Application to overall theoretical design from testing results</li></ul>		Test	Value	Unit
		pH	8.03	
		Turbidity	1.83	NTU
		Conductivity	749.8	uS/cm
		Ammonia	0.000	mg/L NH3
		Nitrate	0.245	mg/L NO3-
		Nitrite	0.000	mg/L NO2-
		Alkalinity	187	mg/L CaCO3
		TOC	2.53	ppm
		DIC	44.2	ppm


### Final Design, Testing Method, and Models



### Testing Process Diagram




### Electrical Design



### Main Component Loads and Voltages

Generator	131 MW/13.8 kV
Motor	91.5 MW/13.8 kV
Facility Auxiliary	10.8 kW/120 V
Equipment Auxiliary	410 kW/480 V

### Cybersecurity and Controls



### Key Considerations

- Facility availability and communication integrity prioritized
- Redundancies in digital systems and defenses provide security
- Sensors and logging alert operators of unexpected activity